20’ wide x 44’ Double Pitch, glass
Structural skylight system
set on wood curbs and end walls

Metal Roofing with wood joists
and hardie plank ceiling

Exhaust Fan

Radiant gas heaters

Florescent Lighting

Mesh Ceiling

4” dia. welded steel tube frame
with cable mesh infill

Steel Column

Research
Porch

Mesh Wall
with Computer

Day Rooms

Isolation
Enclosure
12’ x 32’

17’

10’

CMU wall systems
Smooth, colored
block

Sleeping
Rooms

CMU wall

Mesh Cagefront

Overhead Transfer Chute

5’ overhang

2’-6” x 3’ h.
Transfer Doors

3’ Deep Mulch
Bedding

8’ keeper aisle
center drain

3’ Deep Mulch
Bedding

10” x 2’ high
concrete perimeter curb
with earth floor

20’
Skylight

34’ o.c.

Ursa International

APE COGNITION
& CONSERVATION
INITIATIVE

Bonobo Center

Section A: Holding Building

1/4” = 1’-0”

0 2’ 4’ 6’ 12’

10.2216